جامعة خليفة
Khalifa University

EMERGENCY PREPAREDNESS

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM

جامعة خليفة
Khalifa University

Title of Document : Emergency Preparedness
Document No. : KU – FD – EHS – MPM – 03

Issue No. : 01
Issue Date : 19/11/2012

Revision No. : 01
Revision Date : 07/06/2018

Activity	Name / Designation	Signature	Date
Prepared by	Roberto Macahig EHS Inspector		04/03/2018
Reviewed / Updated by	Fadi Al Jallad EHSS Compliance		09/04/2018
Endorsed for Approval by	Belal Irshaid EHSS Manager		15/05/2018
Approval & Issue by	Hamza Kazim Facilities, Administration & EHSS Vice President		07/06/2018

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM

جامعة خليفة
Khalifa University

CONTENTS

1. PURPOSE: 4

2. SCOPE: 4

3. RESPONSIBILITIES: 4

4. ABBREVIATION / DEFINITIONS: 5

5. PROCEDURE: 5

5.1 SAFETY CONTROL MEASURES: 5

5.2 ROUTINE INSPECTION AND MAINTENANCE OF THE FIRE SAFETY INSTALLATIONS: 13

5.3 EXTENSION AND ALTERATION: 19

5.4 MONITORING AND REVIEWING: 20

6. REFERENCE STANDARDS: 21

7. ANNEXURE: 21

8. RECORDS / DOCUMENTS / FORMATS: 21

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM

1. Purpose:

This procedure it is essential for the safety of the occupants of a building that fire safety equipment is checked frequently. Although much of the checking can be undertaken by suitably trained personnel, a formal agreement should be done with the installer, his agent, or an accredited servicing organization, to provide regular inspection and testing.

2. Scope:

KU Abu Dhabi, Sharjah main building and premises should follow this procedure to maintain a safe climate to prevent or mitigate emergencies and any fire related occurrences.

3. Responsibilities:

3.1 EHS Steering Committee Representative: Responsible for

- Ensure an effective implementation of this procedure in KU, Sharjah main building and all KU premises.
- Report to top management on the performance of this procedure and any need for continual improvement.

3.2 EHS Manager: Responsible for:

- Ensure that this procedure is implemented and maintained.
- Overall performance monitoring of this procedure.

3.3 EHS Emergency Management Committee/Team: Responsible for:

- Review all records of this procedure e.g. Emergency Preparedness Log Book Register.
- Analyze all incidents regarding the emergency preparedness prior to the periodic updating of risk register and provide necessary advice to Facility management Department.
- Provide and enhance the existing guidelines to the Facility Management Department to enforce the monitoring and implementation of such procedure.

3.4 Facility Management Department Coordinator: Responsible for:

- Ensure that all necessary control measures identified and recorded in the Emergency Preparedness Log Book Register.
- Monitoring of effectiveness of this procedure.
- Reporting to the EHS Emergency Management Committee/Team and provide proper information.
- Conduct a regular inspection a companied with contractors.

4. Abbreviation / Definitions:

EHSSC	EHS Steering Committee Representatives
EMC/T	EHS Emergency Management Committee/Team
EHSMS	Environment, Health and Safety Management System
MSM	Management System Manual
MPM	Management Procedure Manual
ALARP	As Low As Reasonable Practicable

5. Procedure:

5.1 Safety Control Measures:

5.1.1 Emergency Control Room:

The Emergency Control Room contains the following:

- All control and indication equipment for the fire alarm and other fire safety systems for the building.
- Indicator panels showing the location of the incident and status of all automatic fire protection installations and facilities;
- Manual override switches associated with all automatic fire protection installations and facilities;
- Manual overrides for air conditioning systems or ventilation systems involving recirculation;
- An exchange telephone with direct dialing for external calls;
- A public address system;
- The fire routine for the building;
- Keys or other devices needed to facilitate access throughout the building and to operate any mechanical and electrical systems;
- Floor plans of the building and external emergency numbers.
- Telephone numbers of principal staff/building services engineers;
- A facility to sound the evacuation signal in each evacuation zone by individual switches;
- A facility to sound the alert signal throughout the building;
- A visual indication of status of relevant floors i.e. those floors in which an evacuation signal has been given;

- A facility to cancel any automatic sequencing of phases but not the initial phase;
- A wall mounted writing board with suitable writing implements for displaying important information.
- The control center shall be staffed by a competent person, familiar with the use and operation of the equipment contained therein, while the building is occupied.

5.1.2 Automatic Fire Detection:

- Early detection of a fire and the raising of an alarm have obvious advantages. They increase the possibility of a successful attack on a fire which is still relatively small.
- In spaces where smoke control and/or other automatic fire protection devices are employed the automatic fire detection system are zoned in accordance with the zoning arrangements for those facilities in the KU main building.

5.1.2.1 Smoke detectors:

- Is a device that senses visible or invisible particles of combustion?
- Smoke detectors are located in various areas in KU main building e.g. all corridors, lobbies, all electrical rooms, Council Chamber, workshops, computer training center, President Office, VP office, Undersecretary office, Director's office, etc.

5.1.2.2 Heat Detectors:

- Located in pump rooms and some kitchen.

5.1.3 Fire Alarm Systems:

The raising of an alarm enables prompt information and instructions to be given to the building occupants – thus preventing a premature mass evacuation.

5.1.3 .1 The following devices are available in support of the alarm and detection system:

- Main control panel;
- Repeat panel;
- Ionizing smoke detectors;

- Heat detectors;
- Addressable manual break glass call points; and
- Fire alarm bells;
- Fire alarm printed circuit board (PCB);and
- Fire alarm PC (in the main panel of each building block).

5.1.3 .2 The fire alarm will be activated by the following:

- Break glass call point;
- Any sprinkler flow switch or any other automatic fire extinguishing system;
- Manual operation at the Emergency Control Centre;
- Any automatic fire detection.

5.1.4 Fire suppression Systems:

The KU main building Fire Protection System is installed in accordance with the NFPA standards and approved by the local Civil Defense authorities. The system consists of but not limited to the following:

- Wet riser system
- Wet pipe sprinkler system (in specific areas).

5.1.4 .1 Riser and Hose System:

- The wet riser system including valves, hose and accessories is installed in conformance with the Civil Defense authorities to serve the fire hose cabinets.
- Each cabinet contains red rubber fire hose (of 30m length, 25mm diameter) with an automatic valve to open water flow after 2.5 turns of the reel.

5.1.4 .2 Sprinkler System:

- In addition to the manual fire-fighting equipment, part of the building i.e. Municipal Chamber, car park etc. is protected by automatic wet pipe sprinkler system and designed based on ordinary hazard occupancy.
- ” Ordinary Hazards” are classified as those that are likely to burn with moderate rapidity or to give off a considerable volume of smoke “.

5.1.4 .3 Portable Fire Extinguishers:

- The use of the proper type of extinguisher for each class of fire will give the best control of the situation.
- Portable fire extinguishers are distributed throughout the KU main building in accordance with Civil Defense authorities and as prescribed in NFPA.
- Portable firefighting equipment enables trained staff to tackle a fire whilst the Civil Defense on the way.

5.1.4 .4 Type of Fire Extinguishers:

- **Class A extinguishers:** Contain water under pressure and should be used only on class a fires.

  NEVER USE CLASS 'A' ON AN ELECTRICAL FIRES.
- **Class BC extinguishers:** Contain CO2 and may be used on class B (flammable liquids) or class C (elect) fires.
- **Class ABC extinguishers:** Contain a dry chemical powder and may be used in any class fire. (But not appropriate for grease fire).

5.1.4 .5 Computer Room:

- Computer rooms shall be equipped with clear extinguishing agent class BC in accordance with NFPA. Dry chemical should be used.
- Very Early Smoke Detection and Alarm System "VESDA "will be installed in the computer room and the UPS room.

5.1.5 Smoke Control Provision:

- The initial aim of smoke control is to raise smoke above head height by venting smoke, by direct means to the external atmosphere, to enable the occupants of the building to escape safely in the event of a fire occurring anywhere in the building based on limiting the travel distance and providing, where necessary, protected escape routes.
- The measures in those sections for smoke control in corridors and protected escape routes are based on the principle of containment.

5.1.5 .1 Smoke control in the KU main building is used for:

- The protection of means of escape;
- Assistance to the Civil Defense during firefighting operations;

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM

- Damage control.
- These needs are considered to be met under normal circumstances by the provision of fire resisting enclosures and fire resisting self-closing doors.

5.1.6 Public Address System:

- Provide accurate information to the occupants of a building relating to the nature of the incident and the action being taken to render it safe.
- This will be done on the first stage (announcement) to maintain calm & prevent possible premature evacuation.
- Audible throughout and capable of communicating with all parts of the building simultaneously or with individual areas/floors.
- The control of the public address system is located adjacent to the fire alarm control panels in the Emergency Control Room.

5.1.7 Lifts:

- Generally 9 lifts are connected to the fire alarm system which will activate lift inhibitors ensuring lifts are lowered to ground floor, open their doors and remain open until being manually reset.
- Experience in fires has shown that misuse or malfunctioning of lifts has caused a number of deaths, attributed amongst other things to failure of the power supply or lifts being called to or held at the fire floor
- For these reasons it is not appropriate to use passenger lifts for means of escape. For the same reasons, it is not appropriate to use the goods and service lifts in the event of fire.

5.1.8 Internal Fire Exit Doors:

- Protect staircases from smoke in case of fire;
- Exit is a mean of escape and should be clear, unobstructed and operable;
- All exit doors are labeled;
- All pathways and exits are properly illuminated;
- Always shall be functional;
- Always shall be kept closed (not locked);

- Exit door that is held partially/ are not closed properly shall be reported immediately to floor Fire Marshal or his deputy.

5.1.9 Automatic Internal Fire Compartmentation Doors:

- Are installed in corridors to separate zones for fire/smoke prevention/protection;
- Their purpose also is to confine the fire/smoke and assist in case of evacuation;
- Installed and shall be fully functional;
- Are connected to the main alarm system (if alarm is activated doors automatically closed).

5.1.10 External Exit Door:

- Shall be clear, unobstructed and operable;
- All exits should be labeled;
- Shall open outwards;
- Shall not to be locked;
- Shall be fully functional;
- Shall not to rely on any kind of electrical back-up or keys;
- Any defect shall be reported immediately to floor Sr. Fire Marshal;

5.1.11 Escape Staircases:

- Staircases are structured and protected as the approved means of egress from all floors (are the only route of escape from the above floors);
- Stairs are equipped with handrails of approved height and width and continue for the full length of each flight of stairs;
- Shall always be designed as a sealed unit preventing any influx of smoke

5.1.12 Emergency Lighting:

- Automatic power change over system is available ;
- Emergency generators supply emergency lighting to all exit corridors of the building;
- Emergency lighting is linked to the main control breaker;

- Periodic functional testing of emergency lighting is conducted;
- Written records of tests and visual inspections are maintained.

5.1.13 Air conditioning:

Generally- the whole building installation is connected to an auto shut down system, connected to the alarm system

5.1.14 Signage and Notices:

Positions of directional Signage, emergency / evacuation notices, stair case exit doors Signage and Assembly point's Signage for the evacuation plan (working drawing) are provided.

5.1.15 Assembly Points:

- During an emergency evacuation of the building, designated assembly areas are utilized;
- Assembly point signs are posted in the designated areas;
- All personnel, emergency personnel and security guards must be familiar with those locations at all times;
- Designated Fire Marshals on each floor will provide instructions to all floor occupants on the assembly assigned locations and on any temporary or permanent changes.

5.1.16 Communication and Facilities for Civil Defense:

- It is essential that the Civil Defense is alerted in every emergency;
- This can be done in a number of ways, usually by dialing 997 telephone system;
- In the Emergency Control Room provision is made for telephone communication with all public emergency services and to independent of all other telephone traffic.
- Good communication between firefighters at the scene of an incident are vital to successful fire-fighting;
- Early consultation with the Civil Defense and local authorities to identify and remedy potential difficulties in providing facilities to assist the Civil Defense;
- Roadways are constructed to allow access for fire appliances;
- Entry points to the building are readily identifiable to the Civil Defense.

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM

5.1.17 Electrical Services:

All electrical services are installed, periodically inspected maintained and tested by suitably and competent qualified engineers and technicians.

5.1.17 .1 Electrical Power Supplies to Life Safety and Fire Protection Equipment:

- All power supplies to life safety and fire protection equipment, and their associated control equipment back to the origin of the supply within the building are regarded as being within the hazard risk area. Therefore great care is being taken to ensure power is available at all times;
- Consideration also are given, not only to the routing of cables, but to position terminations, circuit protection facilities and control panels, to ensure that these are also provided with protection from the effects of fire;
- Each connection to the power supply is via an isolating protective device reserved solely for the life safety and fire protection equipment and independent of any other main or sub-main circuit. They are secured against unauthorized operation and are, except for maintenance, kept locked-on;
- In Emergency Control Room monitoring facilities are provided to show, as far as is reasonably practical, that power is available up to the final control point, to all fire safety systems.

5.1.17 .2 Protected Circuits for Operation of Equipment in the Event of Fire:

- Wiring systems for the power supply to electrical equipment required to operate in the event of fire are of a type or installed in a manner such that, the circuits will continue to operate and the cables will maintain circuit integrity;
- Are protected against exposure to the fire by separation from any significant fire risk by a wall, partition or floor with a fire resistance of not less than that required for the building;
- The wiring systems are protected from mechanical damage.

5.1.17 .3 Primary and Secondary Power Supplies:

- To reduce the risk of the loss of electrical supply in a fire, a secondary power supply is provided;

- This supply is for emergency generators which is of sufficient capacity to maintain supplies to the life safety installations including fire safety systems;
- The changeover from the primary to the secondary power supply is automatic so that the life safety installations continue operation.
- A secondary power supply i.e. an automatically started generators, are provided which will maintain in operation: wet riser pumps, sprinkler pumps and other fire protection of fire-fighting equipment; except automatic fire detection and alarm systems.

5.2 Routine Inspection and Maintenance of the Fire Safety installations:

5.2.1 Daily checks: The daily check recommended should be carried out.

5.2.1.1 Fire detection and alarm systems: The following should be checked:

- The control panel that indicates normal operation and, if any fault is indicated, that it is logged and the appropriate action(s) taken;
- That any fault recorded the previous day has received.

5.2.1.2 Emergency and escape lighting systems: The following should be checked:

- That every lamp is lit if the system is a maintained lighting system;
- That the control panel for any central generator indicates normal operation;
- That any fault found is logged and the appropriate action(s) taken.

5.2.1.3 Sprinkler systems:

Unless automatically controlled. The water level and air pressure in any pressure tank providing a duplicate water supply; and any necessary corrective action(s) should be taken.

5.2.1.4 Fire door automatic release mechanisms:

All doors held open by automatic release mechanisms should be checked by releasing them.

5.2.1.5 Portable fire extinguishers and hose reels:
Checking should be carried out to ascertain that all portable fire extinguishers and hose reels are in place and not obstructed, discharged or damaged.

Note: Any extinguishers used in a fire, or for training, should be recharged immediately.

5.2.2 Weekly checks: These checks are additional to the daily checks listed.

5.2.2.1 Fire detection and alarm systems: The following should be checked

- The Ability of the control equipment to receive a fire signal and to initiate the evacuation procedure, recording which trigger device has been used, and ensuring that each zone is tested at least every 3 months.
- That any standby batteries are in good condition and that the fuel, oil and coolant levels of any standby generators are correct, topping up as necessary.

5.2.2.2 Sprinkler Systems: The following should be checked:

- Water and air pressure gauge reading on installations, trunk mains and pressure tanks, and water levels in elevated private reservoirs, water storage tanks, and all gauge readings and levels recorded.
- That each water motor alarm has been sounded for at least 30s.
- Fuel and oil levels of diesel engines used to power automatic pumps,
- That automatic pumps start when the water pressure is reduced to the specified level and, if powered by a diesel engine, the oil pressure, the following of cooling water through open –circuit cooling systems or the water level in the primary circuit of closed-circuit cooling systems, and whether the engine will restart, using the manual start test button.

5.2.2.3 Gaseous, powder extinguishing systems: The following should be checked:

- Any pressure gauges
- That all operating controls are both properly set and accessible,
- That all indicators are functioning.

- That the equipment, particularly pipe work and nozzles, is free from dust and dirt, is neither physically damaged nor leaking, and remains in its designed position.
- That the fire risk and its enclosure have not changed.
- That the quantity of extinguishing medium is correct and, for wet systems, that the water supply is available and at the correct pressure.

5.2.2.4 Smoke control systems for means of escape:

Actuation of the system should be simulated and it should be ascertained that any fans and powered exhaust ventilators operate correctly, smoke dampers close (or open in some systems), natural exhaust ventilators open, etc.

5.2.2.5 Fire hydrants:

Checks should be carried out to ascertain that there are no obstructions impeding accessible, that the indicator plates are in position, and that the isolating valves are locked open.

5.2.2.6 Hose reels:

Check that water is still reaching the equipment.

5.2.3 Monthly checks: These checks are additional to the weekly checks listed

5.2.3.1 Fire detection and alarm systems:

Any standby generator should be started up (by simulating failure of the normal power supply) and allowed to energize the system for at least 1h, while the system is monitored for any malfunctioning the normal supply, the charging arrangements for the generator starting battery should be checked to ascertain that they are functioning correctly, the oil and coolant levels should be topped up, and the fuel tanks filled.

5.2.3.2 Emergency and escape lighting systems: The following should be checked:

- After simulating a failure of the supply to the normal lighting, that all luminaries and exit signs function correctly If the standby supply is from a generator, that all luminaries and exit signs function correctly even if the generator is prevented from starting;

- After restoring the supply to the normal lighting, that:

1) Indicator lamps or devices to self-contained luminaries or internally illuminated exit signs show that normal supply has been restored;
2) The charging arrangements for any battery for starting a generator are functioning correctly, that the oil and coolant levels have been topped up, and that the fuel tanks are filled.

5.2.3.3 Gaseous, powder extinguishing systems:

Checks should be made that all personnel who may have to operate the equipment or system(s) are properly trained and authorized to do so.

5.2.3.4 Hose reels:

Hose reels should be checked for leaks, and to ascertain that drum assemblies are free to rotate on their spindles.

5.2.3.5 Automatic opening doors:

The operation of the fail-safe mechanisms should be checked either by 'breaking-out' the door set or by simulating failure of the mains power supply, as appropriate.

5.2.4 Three-monthly checks: These checks are additional to the monthly checks listed

5.2.4.1 Smoke control systems to assist firefighting:

Actuation of the system should be simulated in order to ascertain that any fans and powered exhaust ventilators operate correctly, smoke dampers close (or open in some systems), etc.

5.2.4.2 Three-monthly inspections and tests:

Arrangements should be made for quarterly inspections and tests of the fire detection and alarm and the sprinkler systems to be carried out by competent persons, for any defects found to be logged and the necessary action taken. It should be ensured that certificates of satisfactory testing are received.

5.2.5 Six-monthly checks: These checks are additional to the three-monthly checks listed

5.2.5 .1 Fire doors: The following should be checked:

- That heat-activated seals and smoke seals are undamaged;
- That door leaves are not structurally damaged or excessively bowed or deformed;
- That gap between the door leaf and the frame are not so small as to be likely to bend, or so large as to prevent effective fire and smoke-sealing;
- That hanging device, securing devices, self-closing devices and automatic release mechanisms are operating correctly.

5.2.5 .2 Fire mains: The following should be checked:

- That inlets, landing valves, drain valves, door hinges and locking arrangements for inlet and landing valve boxes are ready for immediate use, and that spindles, glands and washers are in a satisfactory condition;
- For wet mains:
  - That booster pumps and their associated mechanical and electrical apparatus are functioning correctly;
  - Storage tanks that is full of clean water.

5.2.5 .3 Six-monthly inspections and tests:
Arrangements should be made for these to be carried out by competent persons on the sprinkler system, and extinguishing systems, for any defects found to be logged, and the necessary action to be taken. It should be ensured that certificates of satisfactory testing are received.

5.2.6 Yearly checks: These checks are additional to the six-monthly checks listed
Arrangements should be made for the annual inspections and tests of the following to be carried out by competent persons, for any defects to be carried out by competent persons, for any defects to be logged and the necessary action taken. It should be ensured that certificates of satisfactory testing are received from the civil Defense.

- Fire detection and alarm systems;
- Self-contained luminaries with sealed batteries, if more than 3 years old;
- Sprinkler systems;

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM

- Smoke control systems;
- Fire hydrants;
- Fire mains;
- Portable Fire extinguishers;
- Hose reels.

5.2.7 Three-yearly cheeks: These checks are additional to the monthly checks listed.
Arrangements should be made for three-yearly inspections and tests of the emergency and escape lighting and the sprinkler systems to be carried out by competent persons, for any defects found to be logged and the necessary action taken. It should be ensured that certificates of satisfactory testing are received from the Civil Defense.

5.2.8 Five-yearly cheeks: These checks are additional to the monthly checks listed:
Arrangements should be made to the electrical systems of Fire safety installations to be checked in accordance with the testing and inspection requirements for annul defects found to be logged and the necessary action taken. It should be ensured that certificates of satisfactory testing are received from the Civil Defense.

5.2.9 False or Unwanted Fire Signals:
To demonstrate satisfactory management of false alarms, users must log and categorize the type of false alarm. False alarms fall into one of the following five categories;

1. **Unwanted alarms –** Alarms caused by fumes from cooking, steam, tobacco smoke, dust insects etc.
2. **Equipment false alarms –** Alarms caused by faults with the equipment.
3. **Malicious false alarms –** Alarms arising from the unauthorized or malicious use of the equipment.
4. **False alarms of good intent –** These occur when an individual suspects there is a fire and raises the alarm
5. **False alarms** that do not fall into any of the above categories should be recorded **Unknown.**

Recording this information enables your system installer / service provider to investigate any system faults / problems that you may have with your equipment.

5.3 Extension and Alteration:

- A number of serious fires have occurred during maintenance, alterations and additions to buildings carried out by contractors and subcontracting specialists. Dangers can arise when buildings are in the course of extension and alteration but still partially in use.
- Minor alterations to building design can have a significant influence on the effectiveness of arrangements for the detection and control of smoke. Any intended refurbishment or upgrading of the appropriate authorities with full details of what is proposed.
- Failure to supervise and instruct contractors and subcontractors on the building frequently results in an additional risk of fire.

5.3.1 Rules shall be adopted:

- During maintenance work, and when alterations are being carried out in the building which remain occupied, appropriate arrangements should be made to ensure the safety of escape routes and operation of all fire protection facilities.
- Approval should be obtained from the management, Security and Facility Division and Civil Defense where appropriate, before the implementation of extensions or alterations.
- Management, Security and Facility Division and EHS Division should ensure that arrangements are made for the instruction and supervision of contractors in maintaining fire safety.
- Before any hot work is carried out, hot work permit must filled properly and approved, a thorough safety check should be made in the area concerned and any area to which excessive heat may be conducted, to see that flammable material adjacent to where the work is to be undertaken or any area to which excessive heat may be conducted, are either removed to safety or protected. Portable extinguishers of a type suitable for dealing with any fire arising from hot work should be provided adjacent to the hot work area.
- A further check should be carried out immediately after work has ceased for the day to ensure that the area is safe.
- Effective arrangements should be made to ensure that contractors are briefed the actions to be taken in case of fire and are made familiar with the appropriate escape routes.

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM

5.4 Monitoring and Reviewing:

- The fire safety needs to be reviewed periodically and the procedures set out in it tested.
- The review should include the following:
  1. A review of all plant and equipment interface controls, to ensure that maintenance procedures are being followed;
  2. A review of all staff duties and training procedures;
  3. A check of the record as-built drawings and specifications for all fire protection measures.
- Most of the testing should be a matter of routine activity for the management to ensure that prescribed activities are being properly carried out.
- Regular fire drills should have the following objective:
  1. Providing staff with practical training;
  2. Establishing the effectiveness of training;
  3. Identifying weaknesses in emergency communications procedures;
  4. Assessing the reliability of equipment;
  5. Rehearsing joint action with the Civil Defense.
  6. Satisfying certifying authorities that their requirements are being met.
- Training guideline:
  1. All staff in first month of employment - two instruction periods
  2. Staff on night duties, lone workers and other vulnerable groups, as determined by your risk assessment, should receive yearly refresher training/instruction
  3. Other staff should receive once every two years' refresher training / instruction.
- Staff training/instruction should include the following;
  1. What to do on discovering a fire
  2. What to do on hearing the fire alarm
  3. Location of assembly points

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM

4. How to call the Fire Service

5. Safe use of and fire extinguishers

6. Location of fire alarm calls points and escapes routes.

7. Other specific duties, such as;
   - Making power supplies / plant safe.
   - Evacuating members of the public.
   - Liaising with Emergency Coordinator / Fire Service.

5.4.1 Rules shall be adopted:

- A review of the fire safety should be conducted annually, or whenever alterations are made to the building, in accordance with a documented procedure. Records should be kept of the reviews and of any changes made.
- Inspection routines should make provision for systems installed in the building, such as fire alarms and smoke control equipment.
- There should be a major building evacuation drill at the least once a year.
- The purpose of any test exercise or drill should be clearly defined by management, and explained to the staff, so that it can be assessed afterwards.
- The record of fire drills should be available for scrutiny by the Civil Defense.

6. Reference Standards:

6.1 ISO 14001:2015 Environmental Management System – Requirements.
6.2 ISO 45001:2018 – Occupational Health and Safety Management Systems – Requirements.
6.3 Abu Dhabi Occupational Safety and Health System Framework (OSHAD-SF), EHS RI – CoP 6.0 – Emergency Management Requirements.
6.4 Abu Dhabi Occupational Safety System Framework (OSHAD-SF), EHS RI – CoP 7.0 – Fire Prevention, Planning and Control.

7. Annexure:

7.1 Annexure 1 – Nil

8. Records / Documents / Formats:

8.1 EHS Implementation Plan, Doc. No.: KU – FD – EHS – REG – 03.
8.2 EHS Risk Register, Doc. No.: KU – FD – EHS – REG – 01.

8.3 Emergency Preparedness Log Book No.: KU – FD – EHS – REG – 27.
8.4 Fire Fighting Equipment Form No.: KU – FD – EHS – FOR – 76.
8.5 Sprinkler System Test Form No.: KU – FD – EHS – FOR – 77.
8.6 Fire Alarm Test Form No.: KU – FD – EHS – FOR – 78.
8.7 False/Unwanted Fire Signal No.: KU – FD – EHS – FOR – 79.
8.8 Miscellaneous Provision Form No.: KU – FD – EHS – FOR – 80.
8.9 Fire Safety Inspections and Audits Form No.: KU – FD – EHS – FOR – 81.
8.10 Monthly Fire Safety Inspection Checklist No.: KU – FD – EHS – CHE – 09.
8.11 Emergency Light System Test Form No.: KU – FD – EHS – FOR – 75.

جامعة خليفة
Khalifa University

Record of Reviews & Revisions

REV.	DATE ISSUED	DESCRIPTION OF REVISION		REVIEWED BY	AUTHORIZED BY
		PAGE NO	COMMENT		
01	07/06/2018	All	Change of logo	Roberto M.	Belal I.
		Throughout	Change from KUSTAR to KU	Roberto M.	Belal I.
		Throughout	Change the reference from AD EHSMS to OSHAD SF	Roberto M.	Belal I.
		02	Prepared by Reviewed / Updated by, Endorsed for Approval by, and Approval & Issue by	Roberto M.	Belal I.
		21	Change the reference from AD EHS Center to OSHAD	Roberto M.	Belal I.
		21	Reference Standard from ISO 14001:2004 to ISO 14001:2015	Roberto M.	Belal I.
		21	Reference Standard from OHSAS 18001 2007 to ISO 45001:2018	Roberto M.	Belal I.

Copies of this document available in KU EHS Intranet are only the latest, valid and controlled documents. All other copies are uncontrolled and valid only on the date printed. Last printed: 7/6/2020 2:30:00 PM